

UNCLASSIFIED

AD NUMBER

AD341090

CLASSIFICATION CHANGES

TO: unclassified

FROM: secret

LIMITATION CHANGES

TO:

Approved for public release, distribution unlimited

FROM:

Distribution limited to U.S. Government Agencies and their Contractors; Specific authority; Not releasable to foreign nationals.

AUTHORITY

DTRA ltr, 6 May 99; DTRA ltr, 6 May 99

THIS PAGE IS UNCLASSIFIED

SECRET
RESTRICTED DATA

AD 341 090L

DEFENSE DOCUMENTATION CENTER

FOR

SCIENTIFIC AND TECHNICAL INFORMATION

CAMERON STATION, ALEXANDRIA, VIRGINIA



RESTRICTED DATA
SECRET

NOTICE: When government or other drawings, specifications or other data are used for any purpose other than in connection with a definitely related government procurement operation, the U. S. Government thereby incurs no responsibility, nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use or sell any patented invention that may in any way be related thereto.

NOTICE:

THIS DOCUMENT CONTAINS INFORMATION
AFFECTING THE NATIONAL DEFENSE OF
THE UNITED STATES WITHIN THE MEAN-
ING OF THE ESPIONAGE LAWS, TITLE 18,
U.S.C., SECTIONS 793 and 794. THE
TRANSMISSION OR THE REVELATION OF
ITS CONTENTS IN ANY MANNER TO AN
UNAUTHORIZED PERSON IS PROHIBITED
BY LAW.

S E C R E T

RESTRICTED DATA

ATOMIC ENERGY ACT 1954

U.S. AIR FORCE

Project

RESEARCH

RAND

MEMORANDUM

987706L

341090

AD No.

DDC FILE COPY

This material contains information affecting the national defense of the United States within the meaning of the espionage laws, Title 18 U.S.C., Secs. 793 and 794, the transmission or the revelation of which in any manner to an unauthorized person is prohibited by law.

AIR FORCE
BALLISTIC MISSILE DIVISION

TECHNICAL LIBRARY

SEE TITLE PAGE FOR DISTRIBUTION RESTRICTIONS

Document No. *7706L*

Copy No. *1*

This is a working paper. Because it may be expanded, modified, or withdrawn at any time, permission to quote or reproduce must be obtained from RAND. The views, conclusions, and recommendations expressed herein do not necessarily reflect the official views or policies of the United States Air Force.

The RAND Corporation

SANTA MONICA • CALIFORNIA

S E C R E T

341090L

43438
8-2640

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT - 1954

AFSWP-1069

U. S. AIR FORCE
PROJECT RAND
RESEARCH MEMORANDUM

/A NEW MODEL FOR FALLOUT CALCULATIONS (U)

R. R. Rapp

RM-2115

13 February 1958

Copy No. _____

This material contains information affecting the national defense of the United States within the meaning of the espionage laws, Title 18 U.S.C., Secs. 793 and 794, the transmission or the revelation of which in any manner to an unauthorized person is prohibited by law.

Assigned to _____

This is a working paper. Because it may be expanded, modified, or withdrawn at any time, permission to quote or reproduce must be obtained from RAND. The views, conclusions, and recommendations expressed herein do not necessarily reflect the official views or policies of the United States Air Force.

DISTRIBUTION RESTRICTIONS

Not suitable for distribution to foreign governments or foreign nationals.

Not suitable for distribution to industrial contractors or commercial organizations.

~~Not suitable for distribution by the Armed Services Technical Information Agency (ASTI), Authority: AFR 209-15~~

The **RAND** *Corporation*

1700 MAIN ST. - SANTA MONICA - CALIFORNIA

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
111

SUMMARY

This paper presents a new model for the machine calculation of fallout patterns. The model is divided into three parts: (1) meteorological, which considers wind velocity and the fall velocity of the particles; (2) geometric, which considers distribution of activity on particles in the cloud as a function of height and particle size; and (3) radiological, which considers the radiation doses of particles on the ground. The use of the model is illustrated, and the changes in the model that will provide an optimum model (currently being developed) are discussed.

RESTRICTED DATA
ATOMIC ENERGY ACT 1954
SECRET

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT--1954

RM-2115
2-13-58
v

CONTENTS

SUMMARY.....	111
Section	
I. INTRODUCTION.....	1
II. FIRST MACHINE MODEL.....	5
III. THE NEW MODEL.....	11
General.....	11
The Meteorologic Calculations.....	11
Errors in Meteorological Part.....	15
Geometric Part.....	18
Preliminary Estimates of the Distribution Functions.....	20
IV. DISCUSSION.....	27
V. CONCLUSIONS.....	31
APPENDIX	
Meteorological Data.....	33
Geometric Data.....	36
REFERENCES.....	45
AFSWP DISTRIBUTION LIST.....	47

SECRET

SECRET

COPY NO.

RAND RESEARCH MEMORANDUM

A NEW MODEL FOR FALLOUT CALCULATIONS (U)

R. R. Rapp

RM-2115

February 13, 1958

in brief

NOTICE: This document contains information affecting the national defense of the United States within the meaning of the Espionage Laws, Title 18, U.S.C., Sections 793 and 794. Its transmission or the revelation of its contents in any manner to an unauthorized person is prohibited by law.

A new model for the machine calculation of fallout described in this Research Memorandum is the latest result of research which began at RAND in 1952. An earlier model to explain the observed facts of radioactive fallout was described in other publications (RM-1855, RM-1371, R-265-AEC, and R-309). The present Research Memorandum describes a new and more flexible computational model to investigate the effect of variations of input data and to discover the effect of parameters. The model is divided into three parts: meteorological, geometric, and radiological.

The initial test of the model was made with the fragmentary Castle-Bravo wind data. The feasibility of the approach has been shown, and the accuracy of the model within the limits of the available data has been verified. The next set of data processed can proceed on the assumptions that;

1. small changes in the distribution functions will produce only negligible changes in the pattern;
2. the wind patterns are sufficiently accurate to put limits on the possible distribution functions;
3. the gross effects of the fallout from large-yield shots are not affected by stem material.

It may be inferred that most of the radioactive material is lodged on particles in a very narrow range of sizes and that it is concentrated into a very narrow range of heights at the time of stabilization.

NOTE: This Research Memorandum is classified SECRET-RESTRICTED DATA. This In Brief is classified SECRET and does not contain any RESTRICTED DATA.

SECRET

The RAND Corporation
1700 Main St. • Santa Monica • California

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
1

I. INTRODUCTION

The process of developing a model that will adequately explain the observed facts of radioactive fallout was begun at RAND in the fall of 1952. The physical process described in reference (1) was the result of those early investigations. The simple mathematical model⁽¹⁾ and the subsequent work of other investigators⁽²⁾ served to confirm the validity of the approach to the problem. Procedures were devised for hand computation⁽³⁾ and machine computation⁽⁴⁾ which further confirmed the basic principles but also served to show that there were deficiencies in the input data. To investigate adequately the effect of variations of input data and to discover the effect of variation of parameters a new, more flexible computational model was needed. This report deals with the development of such a model.

Before presenting the development of the new model it may be profitable to review briefly the physical concepts and the first machine model. To describe the phenomenon of fallout, we must begin with the nuclear detonation. The main distinguishing feature of a detonation of this type is a tremendous release of energy almost instantaneously and within a very small space. This release of energy creates a hot bubble of air which rises because of its bouyancy. The characteristic mushroom-shaped cloud associated with nuclear explosions is formed by water vapor condensed as a result of vertical lifting. The temperature gradient between the hot bubble and the surrounding atmosphere causes a strong toroidal circulation.

Fission fragments, together with any other debris mixed into the fireball at an early stage, are carried aloft, and as the cloud rises some of the material may be left behind, forming a wake or stem. The cloud will stop rising when the energy available to lift it has dissipated. At this time

SECRET

RM-2115
2-13-58
2

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

(from 4 to 6 minutes), which is referred to as the time of stabilization, the spatial distribution of the radioactivity provides one set of the initial conditions required in the fallout model.

Within this stabilized cloud are virtually all the fission products formed by the nuclear detonation and, in some cases, by induced activity. Radioactive particles may be formed by condensation of vaporized material or by the coalescence of fission products with solid or liquid earth particles. The size of the particles is determined largely by the initial conditions of the burst; if little solid material is taken into the cloud, the particles will in all likelihood be small; if, conversely, the device is detonated on or near the surface, many tons of earth will be swept into the cloud, and a sizeable fraction of the fission products will be contained in large particles. The size of the particles containing radioactive elements has an important bearing on the fallout problem. The radioactivity located in or on large particles will be brought rapidly to the ground, while that lodged in small particles will remain suspended in the atmosphere for long periods of time. Another of the initial conditions required in the fallout model, therefore, is the distribution of activity with particle size within the stabilized cloud.

Given the stabilized cloud and the associated distribution of activity with particle size and in space, it is necessary to determine the position of the active particles after they fall to the ground. The rate of fall is of primary importance here, and an aerodynamic law of fall which takes into account, by means of drag coefficients, inertial as well as viscous forces was used.

As the particles start to fall through the atmosphere, they will be

SECRET

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
3

carried by the wind. There are a great many wind effects which have to be taken into account. First, the whole cloud will be moved bodily by the mean wind at the cloud level. At the same time, there will be shearing effects due to the variation of the wind with altitude, and there will be turbulent effects, small scale eddies, which will tend to spread and tear the cloud.

The necessary elements of a fallout model may be summarized:

1. Distribution of activity with space
2. Distribution of activity with particle size
3. Fall velocity
4. Wind structure

SECRET

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
5

II. FIRST MACHINE MODEL

The first machine model used at RAND is reported in detail in reference (4). The cloud was assumed to be a cylinder with a uniform distribution of activity in the horizontal (Fig. 1) and an exponential decrease from the base of the cloud upward (Fig. 2). This decrease with height was predicated on the assumption that the number of active particles per unit mass of air is constant in the mushroom. The uniform horizontal distribution is the most simple of all possible distributions. The distribution of activity with particle size is based on a distribution which reproduced the fallout pattern of the Jangle Surface shot (Fig. 3).

In the model, particles were chosen to represent the fallout at every 1000 ft of elevation at the center of the cloud for values of particle size which divided the activity size distribution into 100 equal intervals. Thus for each elevation, each particle size represented the same amount of activity. The turbulent effects were ignored and the ground position of each particle from each elevation was assumed to represent the center of a circle whose radius was equal to the radius of the stabilized cloud. The activity at a point was calculated by adding the contributions from those circles which contained the point. This system of calculation is fairly efficient insofar as machine time is concerned; however, the method requires a complete recoding for a change in the model because the meteorology is connected to the geometric and particle-size parameters through the choice of particle sizes to be used. The new computation scheme should permit variations of some parts of the model without changing others.

Another feature of the first computation scheme was the incorporation of the decay scheme into the procedure. The activity was assumed to decay

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954




Fig. 1 — Assumed geometry of a cloud resulting
from a large-yield nuclear detonation
(As used in the first RAND machine model)

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

RM 2115
2-13-58
7




Fig.2—Assumed distribution of
radioactivity in space following a
large-yield nuclear detonation
(As used in the first RAND machine model)

SECRET

RM-2115
2-13-58
8

SECRET RESTRICTED DATA

ATOMIC ENERGY ACT 1954




Fig. 3—Cumulative distribution of radioactivity with particle size
(As used in the first RAND machine model)

SECRET

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
9

with the $t^{-1.2}$ law, and the results were transformed to dose rates and integrated doses. While this scheme worked well for fission devices, the variability introduced by clean and salted weapons makes it important to separate the radiological effects from the calculations of particle deposition.

SECRET

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT - 1954

RM-2115
2-13-58
11

III. THE NEW MODEL

A. General

In order to insure flexibility in the new method of computing fallout,* the problem was separated into three component parts. The first part, called the meteorological part, is the determination of the positions on the ground of a fixed set of particles starting from fixed heights in the atmosphere. There are only two sets of the basic variables introduced in this section of the computations, i.e., the fall speed and the velocity of the wind. The second section, which is referred to as the geometric part, is a method for determining the surface density as a function of the density of the stabilized cloud, using the ground distribution of particles. This section involves the distribution of activity with height, radius, and particle size. The third part, which is called the radiological part, deals with the analysis of the radiation dosages that are received from the distribution of activity on the ground. Due to the variable nature of the radiological products no attempt will be made, in this model, to compute radiological effects on the ground.

B. The Meteorologic Calculations

The ground position of a particle falling with a velocity $w(r,h)$ through a wind field $W(x,y,h,t)$ is given by

$$ID = \int_0^H \frac{W(x,y,h,t)}{w(r,h)} dh$$

* In contrast to the first model which was run on the IBM-702, the second model was programmed for and run on the IBM-704 with an augmented memory.

SECRET

RM-2115
2-13-58
12

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

For numerical work this can be expressed as a sum and divided into two component parts

$$X = \sum_{i=0}^m \frac{V_{x1}(x,y,h,t)}{w_1(r,h)} \Delta h_1$$

$$Y = \sum_{i=0}^m \frac{V_{y1}(x,y,h,t)}{w_1(r,h)} \Delta h_1$$

The fall velocities are computed by the aerodynamic methods outlined in the references mentioned.⁽¹⁻⁴⁾ A detailed analysis of the problem of fall velocities will be the subject of another report.⁽⁵⁾ It is sufficient here to state that aerodynamic rates for spheres have been used in accordance with the results of the experiments reported in reference (5). The values of the fall speeds are presented in Fig. 4.

It has been shown⁽⁴⁾⁽⁷⁾ that the time and space variations of the wind are important in predicting fallout, and therefore the model must be able to account for time and space variations. The wind field is really a three-dimensional vector field which is continuous in time and space. To properly take this into account, continuous functions should be used. Unfortunately measurements of the wind field give discrete values of the horizontal component at discrete times. The vertical component cannot be directly measured by any instrument, but it is known to be small compared to the horizontal component. The vertical component will be neglected because it cannot, with current techniques, be calculated with sufficient accuracy.

The east-west and north-south components of the horizontal wind can be measured and will be used separately. Thus, if V_{α} represents one of these components, it can be measured at discrete intervals of space and time. In

SECRET

SECRET
RESTRICTED DATA
 ATOMIC ENERGY ACT--1954

RM-2115
 2-13-58
 13




Fig.4—Fall velocity as a function of height and particle radius

SECRET

SECRET
RESTRICTED DATA
 ATOMIC ENERGY ACT 1954

RM-2115
 2-13-58
 14

order to estimate the wind affecting the particle at any point and at any instant, a four dimensional linear interpolation scheme will be used.

Suppose at time t , the particle is at a height H , at the position ij . Let $V_{\alpha i j k n}$ represent the velocity component in the α direction at the point ij , the height k , and the time n . If there are three points where the wind is known at two times and at intervals of 5000 ft, a first interpolation can be made in elevation:

$$V_{\alpha i j o n} = V_{\alpha i j -1 n} + \frac{H_o - H_{-1}}{H_1 - H_{-1}} (V_{\alpha i j 1 n} - V_{\alpha i j -1 n}) \quad (1)$$

The next interpolation is for position and is given by

$$V_{\alpha o o o} = V_{\alpha 3 3} + \frac{1}{D} \left\{ x (y_1 - y_2) (V_{\alpha 3 3} - V_{\alpha 1 1}) - (y_1 - y_3) (V_{\alpha 2 2} - V_{\alpha 1 1}) \right. \\
+ y (x_1 - x_3) (V_{\alpha 2 2} - V_{\alpha 1 1}) - (x_1 - x_2) (V_{\alpha 3 3} - V_{\alpha 1 1}) \\
+ x_3 (y_1 - y_3) (V_{\alpha 2 2} - V_{\alpha 1 1}) - (y_1 - y_2) (V_{\alpha 3 3} - V_{\alpha 1 1}) \\
\left. + y_3 (x_1 - x_2) (V_{\alpha 3 3} - V_{\alpha 1 1}) - (x_1 - x_3) (V_{\alpha 2 2} - V_{\alpha 1 1}) \right\} \quad (2)$$

where $D = (x_1 - x_2) (y_1 - y_3) - (x_1 - x_3) (y_1 - y_2)$ and "...on" is assumed to be added to the subscripts of all the V 's.

The final interpolation is in time and is given by

$$V_{\alpha o o o o} = V_{\alpha o o o -1} + \frac{t_o - t_{-1}}{t_1 - t_{-1}} (V_{\alpha o o o -1} - V_{\alpha o o o 1}) \quad (3)$$

If this is done for both components x and y , then the velocity at the position of the particle is determined.

With this interpolation process, a particle is started from ground zero, the wind components are computed from Eqs. (1), (2), and (3). These winds are multiplied by a thickness Δh and divided by the mean fall velocity

SECRET

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
15

in the layer; this yields a new position (x,y). The above process is repeated with this new position and a new change in position is computed. The process is repeated until the particle reaches the ground. A total of 7500 particle-height combinations are traced to the ground in this manner.

The time required for a given particle to reach the surface from a given height is also computed from the formula

$$t_d = \int \frac{\Delta h}{w(r,h)} \quad (4)$$

The ground position and time-down for each particle from each height is stored on a tape so that the wind system can be used to check variations in geometry which might arise from variations in yield or burst conditions.

C. Errors in Meteorological Part

It is perhaps worthwhile to form some sort of estimate of the accuracy which may be obtained in the meteorological part of the problem. In order to make this estimate a great many simplifications will be made so that the estimates will yield only the order of magnitude of the wind error.

There are several major assumptions which need to be made in this analysis:

1. Wind errors $\epsilon(c, \sigma_c)$ are distributed according to a circular normal distribution with zero mean and a variance of σ_c^2 .
2. The variance of the errors is not a function of elevation.
3. The correlation of errors is a function only of the separation between winds and decreases rapidly with height difference.
4. For the purposes of this error analysis only, the fall velocities will be approximated by $W = W_0(r)e^{ch}$.

SECRET

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

5. The fall velocities are correct, and no vertical air motion occurs.

Now the calculated position of a given particle will be its actual position plus the integral of the error term

$$D_e = D_a + \int_0^H \frac{\epsilon(o, \sigma_E)}{w(r, h)} dh \quad (5)$$

According to assumption 1, $\bar{\epsilon} = 0$, and $\bar{E} = 0$ but σ_E must be calculated from

$$\sigma_E^2 = \int_0^H \int_0^H \frac{(\epsilon_1 \epsilon_2)}{w(h_1) w(h_2)} dh_1 dh_2 \quad (6)$$

with assumption 2 above this becomes

$$\sigma_E^2 = \sigma_E^2 \int_0^H \int_0^H \frac{\rho_{12}(\Delta h)}{w(h_1) w(h_2)} dh_1 dh_2 \quad (7)$$

where ρ_{12} is the correlation of errors with height. Now in accordance with assumption 3, $\rho_{12} = e^{-\beta \Delta h}$, where β is of the order of 1/2. This means that the correlation is less than 0.1 for separations greater than 5000 feet. According to assumption 4, $w(r, h) = w_1(r) e^{\alpha h}$, where the largest values of α , for 500 μ particles, is about 0.016. Thus β is an order of magnitude greater than α .

Inserting these values in Eq. (7)

$$\sigma_{rf}^2(h) = \frac{\sigma_E^2}{w_o(r)} \int_0^H \int_0^H \frac{e^{-\beta(h_1 - h_2)}}{e^{\alpha h_1} e^{\alpha h_2}} dh_1 dh_2 \quad (8)$$

where the subscript r has been added to the notation for the error variance to indicate that r is treated as a parameter. By making a change of variables

SECRET

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

RM-2115
 2-13-58
 17

$$t = h_1 - h_2$$

$$n = h_1 + h_2$$

Eq. (8) becomes

$$\sigma_{rE}^2 = \frac{\sigma_E^2}{W_0(r)} \int_0^H \int_{-t}^{2H+t} e^{-(\beta t + \alpha n)} ds dt \quad (9)$$

Which, upon integration, becomes

$$\sigma_{rE}^2 = \frac{\sigma_E^2}{\alpha W_0(r)} \left\{ \frac{1}{\beta - \alpha} \left(1 - e^{-(\beta - \alpha)H} \right) - \frac{e^{-2\alpha H}}{\beta + \alpha} \left(1 - e^{-(\beta + \alpha)H} \right) \right\} \quad (10)$$

Now if β is of the order of 0.5 and α is of the order of 0.01, and if H is greater than 10 kilofeet, the terms $e^{-(\beta - \alpha)H}$ and $e^{-(\beta + \alpha)H}$ are small compared to 1 and $\beta - \alpha$ and $\beta + \alpha$ are very nearly equal to β . Therefore, for $H > 10$

kilofeet

$$\sigma_{rE}^2 \approx \frac{\sigma_E^2}{\alpha \beta W_0(r)} (1 - e^{-2\alpha H}) \quad (11)$$

Equation (11) was used to evaluate the ratio of σ_{rE} to σ_E for a few values of r and H in order to provide a means of estimating the expected errors in a fallout pattern. These are shown in Table 1.

Table 1

Ratio of σ_{rE}/σ_E as a Function of Height and Particle Radius

H (kf)	r (μ)			
	24	60	151	600
10	3.101	.747	.243	.063
20	4.160	1.023	.326	.084
30	5.000	1.196	.375	.095
40	5.633	1.321	.412	.105
60	6.578	1.506	.464	.114
80	7.272	1.628	.491	.118
100	7.883	1.701	.512	.118

SECRET

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

RM-2115
 2-13-58
 18

D. Geometric Part

The meteorologic part of the problem provides a method for determining the ground position of many particles originating on many heights over ground zero. If an additional assumption is made, namely some law for the distribution of particles in the horizontal, the ground positions of many particles from many positions in the cloud could be determined. If a fraction of activity per unit volume per unit particle size can be assigned as a function of position in the cloud, then it is possible to determine the fraction per unit area in the fallout pattern.

The first simplification that will be made is to assume that the distribution is radially symmetric about the ground zero position. A second simplification is to assume that turbulent diffusion is not important, so that a particle at a distance R from the ground zero in the cloud would strike the ground at a distance R from the position of a particle of the same size originating over ground zero in the fallout pattern.

Let $A(R, H, r)$ be the fraction of the device per unit volume per unit particle size in the cloud at stabilization. Since A is a fraction or proportion

$$1 = \int_0^{2\pi} \int_0^{R_{\max}} \int_0^{H_{\max}} \int_0^{r_{\max}} A(R, H, r) \, dR \, dH \, dr \, d\theta \quad (12)$$

Since the function of three variables is rather intractable it will also be

SECRET


SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

RM-2115
 2-13-58
 19


assumed that

$$A(R, H, r) = A_1(r) A_2(H) A_3(R) \quad (13)$$

To determine the surface density, consider an arbitrary point $P(x_0, y_0)$ in this fallout pattern. Near this point P there will be found the position of a particle size r_1 , falling from a height H_1 , call this point $B_1(x_1, y_1)$



With the assumption that the cloud composed of particles of size r_1 is not distorted by turbulence, the particles of size r_1 from height H_1 that land at P will come from a point $B_1 = \sqrt{(x_1 - x_0)^2 + (y_1 - y_0)^2}$ distant from the center of the cloud. The volume concentration due to this particle size and this height at the point P is therefore given by $A_1(r_1) A_2(H_1) A_3(R_1)$. Now in a similar way the particle size r_1 may fall from a height H_2 at the point $B_2(x_2, y_2)$ and have a volume concentration of $A_1(r_1) A_2(H_2) A_3(R_2)$



SECRET

RM-7115
2-17-58
20

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

Now all of the particles r_1 from H_1 to H_2 will land at P with radii lying between R_1 and R_2 so that the integration of the activities as determined by the products $A_1 A_2 A_3$ between H_1 and H_2 , will give the surface density of activity at P from particles of size r_1 . A similar argument for another particle size r_2 will yield a surface density due to particles of size r_2 . If the integration is performed over particle size from r_1 to r_2 , the result is the fraction of the device per unit area contributed by all particles between r_1 and r_2 from heights between H_1 and H_2 . If the integration is extended over all r and all H , the total fraction down at P is obtained. The fraction-down per square kilofoot is calculated for a set of pre-chosen grid points P.

It is interesting to note that the geometry of the cloud is expressed by the two distribution functions $A_3(R)$ and $A_2(H)$. At large distances, A_3 reduces to zero and no contribution is made; this continuous distribution is contrasted with the cookie-cutter technique of the first RAND model. The errors introduced through the distribution functions can best be handled by a variation of parameter techniques. Thus several runs may be made using different "A" functions with the same wind patterns, in order to estimate the accuracy of the geometric part.

E. Preliminary Estimates of the Distribution Functions

In an attempt to delineate the distribution of the radioactivity in a stabilized cloud, rockets were shot through some of the Redwing clouds at 7 minutes after detonation. The initial estimates of kiloroentgens per hour at 7 minutes was published in PTR-1354.⁽⁸⁾ It is hoped that, when final reports are prepared, all of the data will be useful. Until such time, the Zuni data will be used to obtain a preliminary estimate of the

SECRET

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
21

distributions.

The Zuni rockets passed very nearly over ground zero and therefore were assumed to represent a vertical plane through the diameter of the cloud. In order to further simplify the problem circular symmetry about ground zero will be assumed. The data were then plotted at the appropriate height and distance from ground zero and smooth contours of the reported rocket readings were drawn (Fig. 5).

From the smoothed contours, the total activity in the cloud was computed by a numerical integration. From the total activity and the smooth contours, the fraction of activity per cubic kilofoot was computed as a function of height and radial distance is shown in Table 2.

The estimate of $A_2(H)$ was chosen as the marginal distribution which is obtained from the numerical integration of $R A(R,H) dR$ at several different heights. This distribution is shown in Fig. (6). The estimate of $A_3(R)$ was chosen as the integration of $A(R,H) dH$ for several different values of R . Figure (7) shows this distribution.

The distribution of activity with particle size was chosen as the distribution presented in reference (1). Accumulative distribution was plotted; points were read from the cumulative function; and numerical differentiation was used to determine values of $A_1(r)$. Since this is a badly skewed distribution, it is convenient to use as a variable $\ln(r)$ instead of r . Figure (8) shows the activity as a function of size for this distribution.

SECRET

RM-2115
2-13-58
22

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954




Fig.5—Results of Zuni rocket measurements (a)
at 7 min with subjective isopleths

SECRET

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
23

Table 2
Debris Concentration (Fraction per Cubic Kilofoot $\times 10^5$) from Rocket Results
as a Function of Radius and Height

Height (kft)	Radius (kft)									
	5	15	25	35	45	55	65	75	85	95
5										
15										
25										
35		1.223	2.751	1.528	.489	.122				
45	.856	1.528	2.45	3.056	1.467	.795	.672	.587	.489	
55	.538	.562	1.223	1.989	.917	.611	.562	.550	.599	.306
65	.245	.306	.367	.428	.367	.306	.245	.061		
75	.061	.183	.245	.183	.122	.122				

SECRET

RM-2115
2-13-58
24

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954




Fig. 6—Smoothed distribution of activity with height from Zuni rocket data

SECRET

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
25




Fig.7—Smoothed distribution of activity with
radial distance from the cloud center from
Zuni rocket data

SECRET

RM-2115
2-13-58
26

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954




Fig.8—Fraction of activity per micron as a function of radius of particle

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
27

IV. DISCUSSION

The initial test of the model, which will be referred to as "run 1," was made with the Castle-Bravo wind data taken from Dean and Ohmstead. The details are presented in the Appendix.

The ground position of a few selected particles, which were read from the results of the meteorological part of the computation, are shown in Fig. (9), which also shows the circular standard errors, derived from the discussion of meteorological errors, with the assumption of an error standard deviation, σ_c , equal to 5 knots. It appears, from this figure, that random errors of this magnitude will not produce large errors in the orientation and general configuration of the pattern. It does seem reasonable to assume, however, that this type of error may cause a considerable error in the fraction of fallout at some point near the boundary of the fallout area. It must be emphasized that these wind error estimates do not include any gross error in defining the vector wind field.

Several variations of the activity functions were tried with the basic wind pattern of run 1. The purpose of these calculations was to make some qualitative estimates of the effect of changing the distribution functions. The details of these calculations are given in the Appendix and are referred to as run 1a, 1b, etc. The inferences which may be drawn from an inspection and comparison of the results of the calculations will be taken up in order.

The difference between runs 1a and 1b was only in the $A_1(r)$ function. The function used in 1b was a log-normal distribution with the same mean and standard deviation as the distribution shown in Fig. (6). The difference between the patterns is not striking. The 1b pattern is not as intense at the hot spot as the 1a pattern, but this was expected since the 1b pattern

SECRET

RM-2115
2-13-58
28

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

SCALE NAUTICAL MILES




Fig. 9—Ground position and circular standard errors of selected particles

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT - 1954

RM-2115
2-13-58
29

had less material concentrated near the mean.

A comparison of runs a and b shows several interesting facts. The largest change is about 30 per cent at the point of maximum deposition in both of the patterns. The log-normal distribution of run lb has fewer particles in the size below 55μ than does the RAND distribution of run la. The distribution used in run lb also shows a higher close-in value than does the run la, indicating too much activity on larger particles.

A comparison of both of these runs with the fragmentary data of the Castle-Bravo shot brings two facts to light. The first point is that both the la and lb distributions show far too large a fraction on the islands of the Bikini Atoll. The second point is that values are low in the northern part of Rongelap.

These errors may be due to an incorrect wind analysis, but they could also be explained by a set of incorrect distribution functions. In any event, the relatively slight change in the patterns between an empirical distribution and a mathematical model seems to be slight. This suggests that an attempt could be made to fit the best possible log-normal, or any other useful function, to the existing data.

Runs lc and ld were made to note the comparison of the old model with the new. Run lc was the mushroom portion, and run ld was the stem; together they reproduce a pattern with essentially the same assumptions as the old RAND model. The pattern for run lc, the mushroom portion, again shows relatively slight differences from runs la and lb. The addition of the stem material from run ld makes little change in the pattern. The greatest contribution from the stem is near ground zero, which is already too high, and near the perimeter of the pattern where the uncertainty is greatest.

SECRET

RM-2115
2-13-58
30

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

A rather drastic change in the distribution of activity with size was made in run 1e. The amount of activity on particles greater than 95μ radius was halved, and this excess was added to the particles between 35μ and 65μ in radius. This run used the same spatial distribution as runs 1a and 1b. The "hotspot" for run 1e was moved far away from ground zero and was reduced in intensity.

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
31

V. CONCLUSIONS

Since the observations on Castle-Bravo were fragmentary, there is no useful purpose to be served by continuing variation of parameters on the set of winds from this shot. The work done has proven the feasibility of the approach and has verified the accuracy of the model within the limits of the available data. It is believed that the next set of data processed can proceed on the assumptions that:

1. small changes in the distribution functions will produce only negligible changes in the pattern;
2. the wind patterns are sufficiently accurate to put limits on the possible distribution functions;
3. the gross effects of the fallout from large-yield shots are not affected by stem material.

It may be inferred that most of the material is lodged on particles in a very narrow range of sizes and that it is concentrated into a very narrow range of heights at the time of stabilization.

The next set of runs will be made on the Zuni shot of Operation Redwing. An attempt will be made to adjust the distribution functions so as to produce calculated values of the fraction-down which are within the range of error measurement at those stations for which adequate measurements are available. This then will be assumed to be the optimum model, and the errors of this model will be assumed to be a minimum for fallout calculations.

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
33

APPENDIX

A. METEOROLOGICAL DATA

Run 1 refers to those fallout calculations that were based on the winds at the time of the Castle-Bravo event. The winds were read from the Dean and Ohmstead charts at 8 locations. Table A1 gives these locations in terms of N-S and E-W distances from ground zero. It was necessary to insure that there were no three points which could be simultaneously colinear and closest to the falling particle, because this situation would invalidate the interpolation functions. The winds were read at two different times (8.25 hours and -15.75 hours from H hour). For times longer than 8.25 hours the wind was assumed to be invariant with time. Table A2 lists the winds at the eight points at two different times.

Table A1

Positions of Points, Relative to Ground Zero,
Where Wind Information was a Machine Input

Point	Distance East (n mi)	Distance North (n mi)
A	- 14	50
B	136	50
C	286	100
D	436	50
E	- 14	-100
F	136	-100
G	286	- 50
H	436	-100

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

Table A2a
Wind Values for Run 1
at 15.75 Hours before Shot Time

Elevation (ft)	Position *											
	A		B		C		D		E		F	
	V	α	V	α	V	α	V	α	V	α	V	α
5,000	07	45	09	52	09	92	10	85	09	75	13	55
10,000	18	305	11	330	13	170	12	130	15	265	10	310
15,000	12	265	11	280	13	214	8	210	12	248	10	289
20,000	15	220	17	250	18	240	18	250	10	220	12	270
25,000	22	233	23	250	23	243	24	250	16	226	17	238
30,000	28	240	29	250	29	245	29	250	22	230	25	225
35,000	28	244	29	254	30	253	32	257	22	233	25	233
40,000	27	250	29	258	31	259	35	264	23	237	25	241
45,000	27	255	30	262	33	265	39	266	24	242	26	248
50,000	27	260	30	265	35	270	42	270	24	245	27	255
55,000	20	264	22	269	25	274	33	273	16	246	18	259
60,000	12	265	24	278	18	283	23	279	08	250	11	268
65,000	02	285	08	302	11	302	14	294	01	349	02	310
70,000	03	50	07	08	08	335	08	335	09	54	07	42
75,000	12	67	12	42	13	40	12	35	17	59	15	56
80,000	20	70	20	55	20	55	20	55	25	60	23	60

* V = Speed (km)
 α = Direction (10's of degrees from N)

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT, 1954

RM-2115
2-13-58
35

Table A2b
Wind Values for Run 1
at 3.25 Hours after Shot Time

Elevation (ft)	Position*													
	A		B		C		D		E		F		G	
	V	α	V	α	V	α	V	α	V	α	V	α	V	α
5,000	09	015	06	110	06	100	08	088	09	062	08	075	10	070
10,000	12	340	10	270	07	280	06	320	10	270	05	230	05	310
15,000	16	303	14	263	12	302	11	317	13	277	08	304	09	343
20,000	23	265	19	290	17	310	17	315	17	280	16	320	13	340
25,000	29	275	25	271	20	271	16	265	16	244	15	264	11	270
30,000	35	270	34	260	30	250	29	250	25	220	25	230	25	220
35,000	40	264	41	260	39	253	38	246	32	220	33	236	32	233
40,000	45	260	46	260	49	255	49	255	39	220	42	240	42	240
45,000	38	266	44	265	45	266	48	268	23	212	23	251	29	262
50,000	32	275	40	270	43	275	50	280	10	180	10	310	25	300
55,000	19	276	24	270	27	272	32	275	03	214	08	288	17	286
60,000	06	280	08	270	12	260	15	260	07	330	08	260	12	260
65,000	04	014	03	345	11	288	06	278	08	039	02	044	03	313
70,000	11	050	09	046	07	005	06	034	15	062	11	066	10	055
75,000	18	057	17	057	15	050	16	055	24	071	21	069	20	065
80,000	25	060	25	060	25	060	25	060	32	075	30	070	30	065

* V = Speed (kn)
 α = Direction (10's of degrees from N)

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

B. GEOMETRIC DATA

Run 1a

In order to adjust the geometric distribution functions A_2 and A_3 to the yield of the Castle-Bravo event, it is necessary to spread the debris over a larger region of space. Since the integrals of the A functions must equal 1, the actual activities must be reduced accordingly. According to Kellogg⁽¹⁰⁾ the cloud diameter of a 3.5 MT device is ~ 20 n mi and a 15 MT device is ~ 29 n mi. Since the Zuni distribution of $A_3(R)$ reduced to nearly zero at ~ 17 n mi (see Fig. 8), it was scaled up to ~ 24 n mi for the Castle-Bravo shot. The activity A_3 was therefore reduced. In a similar way the height of the cloud was increased, and the activity fraction A_2 was decreased.

All of the values of A were tabulated to such a degree that linear interpolation caused less than 1 per cent in the difference between the curves and the interpolated values. The tabulated distribution functions are shown in Table A3.

The machine output gives the fraction of device per square kilofoot at a number of pre-chosen points. The results of this calculation for run 1a are shown in Fig. A1. The isopleths that are drawn on Fig. 9, are subjective estimates of the lines of equal fraction down.

Run 1b

The conditions for run 1b are the same as for run 1a except for the distribution of activity with particle size. The distribution used in run 1b is the log-normal distribution with the same mean and standard deviation as the distribution in run 1a. Table A4 shows the values of $A_1(r)$ as a function of r and also the differences between $A_1(r)$ for run 1a and $A_1(r)$

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
37

Table A3

Activity Function for Run 1a

h (kf)	$A_2(H)$	$r(\mu)$	$A_3(1\mu r)$	$R(n \text{ ml})$	$A(R) \times 10^{-4}$
0	0	9.5	0.15	0	.102
5	.00024	12.25	0.24	.822	.138
10	.00068	15.0	0.33	1.645	.174
15	.00140	20.0	0.41	2.467	.211
20	.00240	24.0	0.66	3.289	.260
25	.00376	31.0	0.93	4.112	.316
30	.00544	38.0	1.19	4.934	.385
35	.00760	49.0	1.37	5.757	.456
40	.01040	60.0	1.42	6.579	.688
45	.01464	77.5	1.41	7.401	.764
50	.02200	95.0	0.68	8.224	.495
55	.03560	123.0	0.43	9.046	.372
60	.04904	151.0	0.27	9.868	.303
65	.03624	195.0	0.19	10.691	.252
70	.00280	239.0	0.20	11.513	.218
75	.01456	309.0	0.16	12.336	.191
80	.00976	379.0	0.11	13.158	.169
85	.00632	489.0	0.06	13.980	.151
90	.00384	600.0	0	14.803	.131
95	.00208			15.625	.117
100	.00128			16.447	.102
				17.270	.089
				18.092	.076
				18.914	.065
				19.937	.054
				20.559	.044
				21.382	.033
				22.204	.023
				23.026	.014
				23.849	.005

SECRET

RM-2115
2-13-58
38

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

2 0 20 40 60
124.5 124.7 124.9 125.1




Fig. A-1—Run Ia, results of calculation
(Fraction of device/Kft X 10⁷)

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
39

for run 1b. Figure A2 shows the fallout computation for run 1b with isopleths subjectively drawn.

Table A4

$A_1(r)$ for Run 1b as a Function of (r) ,
and the Difference between A_1 for Run 1a and A_1 for Run 1b

Index	r	$A_1^b(r)$	$A_1^a - A_1^b$
1	9.5	.280	-.13
6	12.25	.389	-.15
11	15.0	.520	-.19
16	20.0	.648	-.24
21	24.0	.767	-.11
26	31.0	.865	.07
31	38.0	.918	.21
36	49.0	.928	.44
41	60.0	.883	.54
46	77.5	.800	.61
51	95.0	.685	.00
56	123.0	.559	-.13
61	151.0	.427	-.16
66	195.0	.310	-.12
71	239.0	.214	-.01
76	309.0	.140	.02
81	379.0	.086	.02
86	489.0	.051	.01
91	600.0	.028	.03

Run 1c


In order to be able to check the effect of the $A(R)$ and $A(H)$ distributions a model was set up which was similar to the model discussed in reference (1). The exponential decrease with height was assumed for the mushroom and the invariant distribution with R was retained. However 97 per cent of the activity was put into the mushroom, instead of 90 per cent as in the earlier model, and the remaining 3 per cent was used to make up run 1d. The input values are shown in Table A5 and the final pattern is shown in Fig. (A3).

SECRET

RM-2115
2-13-58
40

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

1 2 3 4 5 6 7 8 9 10
11 12 13 14 15 16 17 18 19 20
21 22 23 24 25 26 27 28 29 30
31 32 33 34 35 36 37 38 39 40
41 42 43 44 45 46 47 48 49 50
51 52 53 54 55 56 57 58 59 60
61 62 63 64 65 66 67 68 69 70
71 72 73 74 75 76 77 78 79 80
81 82 83 84 85 86 87 88 89 90
91 92 93 94 95 96 97 98 99 100



SECRET

Fig.A-2—Run 1b, results of calculations
(Fraction of device/ $K_{eff} \times 10^7$)

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
41

1 2 3 4 5 6 7 8 9 10
11 12 13 14 15 16 17 18 19 20
21 22 23 24 25 26 27 28 29 30
31 32 33 34 35 36 37 38 39 40
41 42 43 44 45 46 47 48 49 50
51 52 53 54 55 56 57 58 59 60
61 62 63 64 65 66 67 68 69 70
71 72 73 74 75 76 77 78 79 80
81 82 83 84 85 86 87 88 89 90
91 92 93 94 95 96 97 98 99 100
101 102 103 104 105 106 107 108 109 110
111 112 113 114 115 116 117 118 119 120
121 122 123 124 125 126 127 128 129 130
131 132 133 134 135 136 137 138 139 140
141 142 143 144 145 146 147 148 149 150
151 152 153 154 155 156 157 158 159 160
161 162 163 164 165 166 167 168 169 170
171 172 173 174 175 176 177 178 179 180
181 182 183 184 185 186 187 188 189 190
191 192 193 194 195 196 197 198 199 200
201 202 203 204 205 206 207 208 209 210
211 212 213 214 215 216 217 218 219 220
221 222 223 224 225 226 227 228 229 230
231 232 233 234 235 236 237 238 239 240
241 242 243 244 245 246 247 248 249 250
251 252 253 254 255 256 257 258 259 260
261 262 263 264 265 266 267 268 269 270
271 272 273 274 275 276 277 278 279 280
281 282 283 284 285 286 287 288 289 290
291 292 293 294 295 296 297 298 299 300
301 302 303 304 305 306 307 308 309 310
311 312 313 314 315 316 317 318 319 320
321 322 323 324 325 326 327 328 329 330
331 332 333 334 335 336 337 338 339 340
341 342 343 344 345 346 347 348 349 350
351 352 353 354 355 356 357 358 359 360
361 362 363 364 365 366 367 368 369 370
371 372 373 374 375 376 377 378 379 380
381 382 383 384 385 386 387 388 389 390
391 392 393 394 395 396 397 398 399 400
401 402 403 404 405 406 407 408 409 410
411 412 413 414 415 416 417 418 419 420
421 422 423 424 425 426 427 428 429 430
431 432 433 434 435 436 437 438 439 440
441 442 443 444 445 446 447 448 449 450
451 452 453 454 455 456 457 458 459 460
461 462 463 464 465 466 467 468 469 470
471 472 473 474 475 476 477 478 479 480
481 482 483 484 485 486 487 488 489 490
491 492 493 494 495 496 497 498 499 500
501 502 503 504 505 506 507 508 509 510
511 512 513 514 515 516 517 518 519 520
521 522 523 524 525 526 527 528 529 530
531 532 533 534 535 536 537 538 539 540
541 542 543 544 545 546 547 548 549 550
551 552 553 554 555 556 557 558 559 560
561 562 563 564 565 566 567 568 569 570
571 572 573 574 575 576 577 578 579 580
581 582 583 584 585 586 587 588 589 590
591 592 593 594 595 596 597 598 599 600
601 602 603 604 605 606 607 608 609 610
611 612 613 614 615 616 617 618 619 620
621 622 623 624 625 626 627 628 629 630
631 632 633 634 635 636 637 638 639 640
641 642 643 644 645 646 647 648 649 650
651 652 653 654 655 656 657 658 659 660
661 662 663 664 665 666 667 668 669 670
671 672 673 674 675 676 677 678 679 680
681 682 683 684 685 686 687 688 689 690
691 692 693 694 695 696 697 698 699 700
701 702 703 704 705 706 707 708 709 710
711 712 713 714 715 716 717 718 719 720
721 722 723 724 725 726 727 728 729 730
731 732 733 734 735 736 737 738 739 740
741 742 743 744 745 746 747 748 749 750
751 752 753 754 755 756 757 758 759 760
761 762 763 764 765 766 767 768 769 770
771 772 773 774 775 776 777 778 779 780
781 782 783 784 785 786 787 788 789 790
791 792 793 794 795 796 797 798 799 800
801 802 803 804 805 806 807 808 809 810
811 812 813 814 815 816 817 818 819 820
821 822 823 824 825 826 827 828 829 830
831 832 833 834 835 836 837 838 839 840
841 842 843 844 845 846 847 848 849 850
851 852 853 854 855 856 857 858 859 860
861 862 863 864 865 866 867 868 869 870
871 872 873 874 875 876 877 878 879 880
881 882 883 884 885 886 887 888 889 890
891 892 893 894 895 896 897 898 899 900
901 902 903 904 905 906 907 908 909 910
911 912 913 914 915 916 917 918 919 920
921 922 923 924 925 926 927 928 929 930
931 932 933 934 935 936 937 938 939 940
941 942 943 944 945 946 947 948 949 950
951 952 953 954 955 956 957 958 959 960
961 962 963 964 965 966 967 968 969 970
971 972 973 974 975 976 977 978 979 980
981 982 983 984 985 986 987 988 989 990
991 992 993 994 995 996 997 998 999 1000




Fig.A-3—Run ic, results of calculations
(Fraction of device / Kft X IC7)

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT, 1954

Table A5

Activity Distribution for Run 1c

r	$A_1(r)$	R	$A_2(R)$	h	$A_2(h)$
9.5	0.1455	0	3.513×10^{-5}	0	0
12.25	0.2328	.822	3.513×10^{-5}	5	0
15.0	0.3201	1.645	3.513×10^{-5}	10	0
20.0	0.3977	2.467	3.513×10^{-5}	15	0
24.0	0.6402	2.467	3.513×10^{-5}	20	0
31.0	0.9021	2.467	3.513×10^{-5}	25	0
38.0	1.1543	2.467	3.513×10^{-5}	30	0
49.0	1.3289	2.467	3.513×10^{-5}	35	0
60.0	1.3774	2.467	3.513×10^{-5}	40	0
77.5	1.3677	2.467	3.513×10^{-5}	45	0
95.0	0.6596	2.467	3.513×10^{-5}	50	0
123.0	0.4171	2.467	3.513×10^{-5}	55	0.00560
151.0	0.2619	2.467	3.513×10^{-5}	60	0.04394
195.0	0.1843	2.467	3.513×10^{-5}	65	0.03472
239.0	0.1940	19.737	3.513×10^{-5}	70	0.02743
309.0	0.1552	20.557	0	75	0.02167
379.0	0.1067	20.557	0	80	0.01712
489.0	0.0582	20.557	0	85	0.01353
600.0	0	20.557	0	90	0.01069
		23.849	0	95	0.0084
				100	0.0067

Run 1d

This run was merely the stem portion of run 1c. The total fraction placed in the stem was only 3 per cent, and the addition of this fallout to run 1c made only minor changes in the pattern. In order to get the gross effects of the fallout, it appears unnecessary to be concerned with the stem. In fact even this small amount of stem fallout seemed to increase the error in the pattern in those areas wherein it was detectable.

SECRET

SECRET
RESTRICTED DATA
ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
43

Run 1c

This computation was designed to make a more radical change in the distribution function in order to produce a greater change in the pattern. Since the previous attempts indicated that there was too much debris too close to ground zero, the activity on the larger particles was drastically reduced. The activity size distribution of run 1c is shown in Table A6 and the resulting pattern is shown in Fig. (A4). It may be noted that the activity is spread further down wind than in the other runs, although the maximum has been considerably lowered.

Table A6
The Function $A_1(r)$ for Run 1c

Index	r	$A_1(r)$
1	9.5	0.15
6	12.25	0.24
11	15.0	0.33
16	20.0	0.41
21	24.0	0.66
26	31.0	0.93
31	38.0	1.59
36	49.0	1.77
41	60.0	1.56
46	77.5	1.31
51	95.0	0.34
56	123.0	0.22
61	151.0	0.13
66	195.0	0.10
71	239.0	0.09
76	309.0	0.08
81	379.0	0.05
86	489.0	0.03
91	600.0	0

SECRET

RM-7115
2-13-58
44

SECRET
RESTRICTED DATA

ATOMIC ENERGY OF CANADA

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100




Fig.A-4—Run 1e, results of calculations
(Fraction of device / $Kft \times IC7$)

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
49

REFERENCES

1. Greenfield, S. M., and R. R. Rapp, Fallout Computations and Castle-Bravo - A Case Study(U), Research Memorandum RM-1855, The RAND Corporation, January, 1957, (Secret Restricted Data).
2. Dishington, R. H., A Model for Fallout Calculations(U), Research Memorandum RM-1371, The RAND Corporation, October, 1954, (Confidential).
3. Greenfield, S. M., W. W. Kellogg, F. J. Krieger, and R. R. Rapp, Transport and Early Deposition of Radioactive Debris-Project Aureole(U), Report R-265-AEC, The RAND Corporation, July, 1954, (Secret Restricted Data).
4. AFSWP, 895, Fallout Symposium, Armed Forces Special Weapons Project, January, 1955, (Secret Restricted Data).
5. Rapp, R. R., and J. D. Sartor, Rate of Fall through the Atmosphere of Irregularly Shaped Particles, Research Memorandum RM-2006, The RAND Corporation, November, 1957, (Unclassified).
6. Rapp, R. R., The Vertical Transport of Particulate Matter through the Atmosphere, (To Be Published).
7. Schuert, E. A., "Employment of Time and Space Variable Winds Including Vertical Motions on the Analysis of Particle Trajectories, Appendix E in RAND Fallout Symposium," S-62, April, 1957, (Secret, formerly Restricted Data).
8. Dean, G. A., and W. D. Olmstead, An Example of Three Dimensional Analysis of the Wind Field over the Marshall Islands, Oahu Research Center Institute of Geophysics, University of California, 1954, (Official Use Only).
9. Van Lindt, V.A.J., L. E. Killian, J. A. Chiment, and D. C. Campbell, "Fallout Studies during Operation Redwing," ITR-1354, October, 1956, (Secret Restricted Data).
10. Kellogg, W. W., "Atomic Cloud Height as a Function of Yield and Meteorology," Paper P-881-AEC, The RAND Corporation, June, 1956.

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
47

AFSWP DISTRIBUTION LIST

ARMY

ADDRESSEE	NO OF CYB
Asst Deputy Chief of Staff for Military Operations, D/A, Washington 25, D.C., ATTN: Asst Executive, (R and SW)	1
Chief of Research and Development, D/A, Washington 25, D.C., ATTN: Atomic Division	1
Chief of Ordnance, D/A, Washington 25, D.C., ATTN: ORDTX-AR	2
Chief Signal Officer, Department of the Army P and O Div., Washington 25, D.C., ATTN: SIGRD-8	1
The Surgeon General, D/A, Washington 25, D.C., ATTN: MEDNE	2
Chief Chemical Officer, D/A, Washington 25, D.C.	2
The Quartermaster General, D/A, Washington 25, D.C., ATTN: Research and Development	2
Chief of Engineers, D/A, Washington 25, D.C., ATTN: ENGNE	2
Chief of Transportation, Military Planning and Intelligence Division, Washington 25, D.C.	2
Commanding General, Headquarters, United States Continental Army Command Fort Monroe, Virginia	2
Commanding General, U.S. Army Caribbean, Ft. Amador, Canal Zone, ATTN: Cml Off.	1
Commanding General, Eighth United States Army, APO 301, San Francisco, California, ATTN: ACofS G3	1
Commanding General, U.S. Army Europe, APO 403, New York, N.Y., ATTN: OPOT Div., Combat Dev Branch	2
Commanding General, U.S. Army Pacific, APO 958, San Francisco, Calif., ATTN: Cml Off	2
Commandant, Command and General Staff College, Ft. Leavenworth, Kansas, ATTN: ALIJS(AS)	2
Commandant, Army War College, Carlisle Barracks, Pa., ATTN: Library	1
Commanding General, Army Medical Service School, Brooke Army Medical Center, Ft. Sam Houston, Texas	1

SECRET

RM 2115
2-15-58
48

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

AFSWP DISTRIBUTION LIST

ARMY (CONF'D)

<u>ADDRESSEE</u>	<u>NO OF CYS</u>
Director, Special Weapons Development Office, Headquarters CONARC, Ft. Bliss, Texas	1
Commandant, Chemical Corps School, Chemical Corps Training Command, Ft. McClellan, Alabama	1
Commanding General, U.S. Army Chemical Corps, Research and Development Command, Washington, D.C.	2
Commanding General, The Engineer Center, Ft. Belvoir, Va., ATTN: Asst Cmde, Eng School	1
Commanding Officer, Engineer Research and Development Laboratory, Ft. Belvoir, Va., ATTN: Ch, Tech Int Branch	1
Commanding Officer, Chemical Warfare Laboratories, Army Chemical Center, Maryland, ATTN: Tech Library	2
Director, Technical Documents Center, Evans Signal Lab., Belmar, New Jersey	1
Director, Operations Research Office, Johns Hopkins University, 6935 Arlington Rd., Bethesda 14, Maryland	1
Commanding General, Quartermaster R and D Command, Quartermaster R and D 2 Center, Natick, Mass., ATTN: CDR Liaison Officer	2

NAVY

<u>ADDRESSEE</u>	<u>NO OF CYS</u>
Chief of Naval Operations, D/N, Washington 25, D.C., ATTN: OP-36	2
Chief, Bureau of Medicine and Surgery, D/N, Washington 25, D.C., ATTN: Special Weapons Defense Division	2
Chief, Bureau of Ships, D/N, Washington 25, D.C., ATTN: Code 348	2
Chief, Bureau of Yards and Docks, D/N, Washington 25, D.C., ATTN: Code D 440	1
Chief, Bureau of Supplies and Accounts, D/N, Washington 25, D.C.	1
Chief, Bureau of Aeronautics, D/N, Washington 25, D.C.	2

SECRET

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

RM-2115
2-13-58
49

AFSWP DISTRIBUTION LIST

NAVY (CONT'D)

<u>ADDRESSEE</u>	<u>NO OF CYS</u>
Chief of Naval Research, D/N, Washington 25, D.C., ATTN: Code 811	1
President, U.S. Naval War College, Newport, Rhode Island	1
Superintendent, U.S. Naval Postgraduate School, Monterey, California	1
Commanding Officer, U.S. Naval Radiological Defense Lab., San Francisco, California, ATTN: Tech Info Division	4
Commander-in-Chief Pacific, Pearl Harbor, T.H.	1

AIR FORCE

<u>ADDRESSEE</u>	<u>NO OF CYS</u>
Asst for Atomic Energy, Hq USAF, Washington 25, D.C., ATTN: DCS/O	1
Director of Operations, Hq USAF, Washington 25, D.C., ATTN: Operations Analysis	1
Director of Plans, Hq USAF, Washington 25, D.C., ATTN: War Plans Division	2
Director of Research and Development, DCS/D, Hqs USAF, Washington 25, D.C., ATTN: Combat Components Div	1
The Surgeon General, Hq USAF, Washington 25, D.C., ATTN: Bio Def Br Pre Med Div	1
Commander-in-Chief, Pacific Air Forces, APO 953, San Francisco, California, ATTN: PFCIF-MB, Base Recovery	1
Commander-in-Chief, Strategic Air Command, Offutt AFB, Neb., ATTN: Inspector General, Special Weapons Branch, Inspector Div.	1
Commander Tactical Air Command, Langley AFB, VA., ATTN: Doc Security Branch	1
Research Directorate, Hq Air Force Special Weapons Center, Kirtland AFB, New Mexico, ATTN: Blast EFPS Research	2
Commander, Air Research and Development Command, Andrews AFB, Washington 25, D.C., ATTN: RDDN	1

SECRET

RM-2115
2-13-58
50

SECRET
RESTRICTED DATA

ATOMIC ENERGY ACT 1954

AFSWP DISTRIBUTION LIST

AIR FORCE (CONT'D)

<u>ADDRESSEE</u>	<u>NO OF PGS</u>
Director, Air University Library, Maxwell AFB, Alabama	2
Commandant, Air Force School of Aviation Medicine, Randolph AFB, Texas	2
Commander, MIT Cambridge Research Center, L.G. Hanscom Field, Bedford, Mass., ATTN: CRQST-2	2
Commander, AF Special Weapons Center, Kirtland AFB, New Mexico, ATTN: Library	3

OTHER DOD ACTIVITIES

<u>ADDRESSEE</u>	<u>NO OF PGS</u>
Director, Weapons Systems Evaluation Group, OSD, Rm 2E1006, The Pentagon, Washington 25, D.C.	1
Commander, Field Command, Armed Forces Special Weapons Project, P.O. Box 5100, Albuquerque, New Mexico	1
Commander, Field Command, Armed Forces Special Weapons Project, P. O. Box 5100, Albuquerque, New Mexico, ATTN: Tech TNG Group	1
Chief, Armed Forces Special Weapons Project, Washington 25, D.C.	15

SECRET

<p>The RAND Corporation Santa Monica, Calif.</p>	<p>78-2245</p>	<p>1. NEW MODEL FOR RADIATION TRANSPORTATION. (Reclassified extract, February 13, 1956, Administrative and Santa Monica, California. 57 pp. Incl. illus., references.)</p>	<p>2. NEW MODEL FOR RADIATION TRANSPORTATION. (Reclassified extract, February 13, 1956, Administrative and Santa Monica, California. 57 pp. Incl. illus., references.)</p>
<p>The RAND Corporation Santa Monica, Calif.</p>	<p>78-2245</p>	<p>1. NEW MODEL FOR RADIATION TRANSPORTATION. (Reclassified extract, February 13, 1956, Administrative and Santa Monica, California. 57 pp. Incl. illus., references.)</p>	<p>2. NEW MODEL FOR RADIATION TRANSPORTATION. (Reclassified extract, February 13, 1956, Administrative and Santa Monica, California. 57 pp. Incl. illus., references.)</p>

SECRET
RESTRICTED DATA

RESTRICTED DATA
SECRET



Defense Threat Reduction Agency

45045 Aviation Drive
Dulles, VA 20166-7517

CPWC/TRC

May 6, 1999

MEMORANDUM FOR DEFENSE TECHNICAL INFORMATION CENTER
ATTN: OCQ/MR WILLIAM BUSH

SUBJECT: DOCUMENT REVIEW

The Defense Threat Reduction Agency's Security Office has reviewed and declassified or assigned a new distribution statement:

- AFSWP-1069, AD-341090, STATEMENT A ✓
- ✓DASA-1151, AD-227900, STATEMENT A ✓
- DASA-1355-1, ~~AD-336443~~, STATEMENT A OK
- DASA-1298, AD-285252, STATEMENT A ✓
- DASA-1290, AD-444208, STATEMENT A ✓
- DASA-1271, AD-276892, STATEMENT A ✓
- DASA-1279, AD-281597, STATEMENT A ✓
- DASA-1237, AD-272653, STATEMENT A ✓
- DASA-1246, AD-279670, STATEMENT A ✓
- DASA-1245, AD-419911, STATEMENT A ✓
- DASA-1242, AD-279671, STATEMENT A ✓
- DASA-1256, AD-280809, STATEMENT A ✓
- DASA-1221, AD-243886, STATEMENT A ✓
- DASA-1390, AD-340311, STATEMENT A ✓
- DASA-1283, AD-717097, STATEMENT A OK
- DASA-1285-5, AD-443589, STATEMENT A ✓
- DASA-1714, AD-473132, STATEMENT A ✓
- DASA-2214, AD-854912, STATEMENT A ✓
- DASA-2627, AD-514934, STATEMENT A ✓
- DASA-2651, AD-514615, STATEMENT A ✓
- ~~DASA-2536, AD-876697, STATEMENT A~~
- DASA-2722T-V3, AD-518506, STATEMENT A ✓
- DNA-3042F, AD-525631, STATEMENT A ✓
- DNA-2821Z-1, AD-522555, STATEMENT A ✓

AD waiting for reply

FAD

If you have any questions, please call me at 703-325-1034.

Ardith Jarrett

ARDITH JARRETT
Chief, Technical Resource Center